

BILL OF MATERIAL / QUANTITIES - ELECTRICAL WORK - POONAMALLEE- CHENNAI							Project:	Electrical works	
DATE: 13.03.2026							Client :	YUSEN LOGISTICS (INDIA) PRIVATE LIMITED	
							Quote No:	QUOTE/25-26/1324	
S.No.	Description	Unit	Qty	Materials		Labour		Total	Remarks
				Rate	Total	Rate	Total		
1	Light Fixtures							69,815	
	1 x 18/20W LED light Batten fixture with all required accessories like wooden gata, etc. : IP55. Make : Crompton / Syska/GM	Nos	5	185	925	100	500	1,425	Building inside peripheral lights above the work stations
	1 x 36/40 W LED Downlighter 600 x 600 mm modular type. Make : Crompton / Philips	Nos	26	1,289	33,514	350	9,100	42,614	Ebono office-8 + Meeting room-4+ office room-4+CCTV/ server room-4+Mezanine office - 6 nos.
	Dock Lights: 50 W LED Focus light fixture with all required accessories suitable for fixing on metal surface. Make : Crompton / Sterlite	Nos	6	3,696	22,176	600	3,600	25,776	4 Rolling shutter Including MS Tube structure + 2 New rolling shutter
2	Completion of Earthing work							149,620	
	Copper pipe chemical earthing with 50/ 65mm dia cu clamps funnel complete set etc, and earthing leads.	Nos	1	22,275	22,275	4,500	4,500	26,775	Neutral Power
	GI Pipe earthing with 50 / 65mm dia GI pipe clamps funnel complete set etc, and earthing leads.	Nos	1	4,320	4,320	1,200	1,200	5,520	Panel Body eathing
	25mm x 3mm copper Strip on insulators.	RMT	20	1,620	32,400	65	1,300	33,700	
	25mm x 3mm GI Strip on insulators.	RMT	50	78	3,900	85	4,250	8,150	
	PVC Sleeve	RMT	100	54	5,400	30	3,000	8,400	
	8 SWG GI wire,Hot dip Galvanized conforming to relevant I.S.S. technical specification.	RMT	300	30	9,000	25	7,500	16,500	All DB Body earthing
	2 Runs of 6.0 sqmm PVC insulated copper wires of 660v grade in 2mm thick PVC conduit	RMT	60	560	33,600	35	2,100	35,700	
	Rubber mat (1100V grade) of sufficient thickness as required by the electrical inspectorate. 2.5mm thick class B suitable up to 11KV Size 1M x 2M -1 No	S.qm	7	2,025	14,175	100	700	14,875	Electrical Panel room + UPS room
4	Sub Main Wiring							242,370	
	2C X 1.5 sqmmFlexible cable in PVC conduit. Make: Polycab / Orbit	RMT	300	148	44,400	60	18,000	62,400	Tubelights+ office
	3C X 1.5 sqmm Flexible cable in PVC conduit. Make: Polycab / Orbit	RMT	300	254	76,200	60	18,000	94,200	Industrial fan+ Floor workstation Power point + Office WS wiring + Network rack power point + Others
	2 runs of 2.5 sqmm + 1 run of 1.5 sqmm (for phase , neutral & earthing) PVC insulated copper wires. Make: Polycab / Orbit	RMT			-		-	-	AC + Air curtain
	2 runs of 4.0 sqmm & 1 Run of 1.5sq.mm. (for phase , neutral & earthing) PVC insulated copper wires in 25mm dia PVC conduit. Make: Polycab / Orbit	RMT	200	258	51,600	60	12,000	63,600	Crate washing area motor Pump wiring.
	2 runs Of 16.0 Sqmm copper conductor wires & 1 run of 2.5sq.mm.(for phases, Neutral & earthing) in 25 mm dia PVC Conduit. Make: Polycab / Orbit	RMT	30	671	20,130	68	2,040	22,170	UPS I/P & O/P cabling work
5	Point Wiring							16,482	
	Single light point controlled by one No.6Amps Modular key type SP Switch. Make: Anchor Roma / GM	Pts	15	339	5,085	195	2,925	8,010	
	Two light point controlled by one No.6Amps Modular key type SP Switch. Make: Anchor Roma / GM	Pts	8	486	3,888	228	1,824	5,712	
	Three light point controlled by one No.6Amps Modular key type SP Switch. Make: Anchor Roma / GM	Pts	3	660	1,980	260	780	2,760	
6	Distribution Boards - Make : Schneider / ABB							82,563	
	6 way PPI TPN DD DB with 'C' curve MCB INCOMING : 1 no. 40/63 A 4P MCB, Phase wise - 3 nos, 2 Pole, 30mA ELCB OUTGOING : 12 nos. 6-20A SP MCBs	Each	1	14,633	14,633	2,000	2,000	16,633	Raw Power DB
	DB 4 way TPN DD DB with 'C' curve MCB INCOMING : 1 no. 63 A 2P MCB OUTGOING :6 nos. 40A DP MCBs	Each	1	9,846	9,846	1,800	1,800	11,646	ALL AC Power DB
	8 way SPN DB with 'C' curve MCB INCOMING : 1 no. 40A DP MCB 1 no. 30mA SPN ELCB OUTGOING : 6 nos. 6-20A SP MCB's	Each	3	3,702	11,106	1,500	4,500	15,606	UPS Power distribution DB for office / Floor
	Power DB 4 way Vertical TPN DD DB with 'C' curve MCB INCOMING : 100 A TPN MCCB - 1NOS OUTGOING : 4 nos. 20--32A TP MCBs	Each	2	16,839	33,678	2,500	5,000	38,678	Cold room + Crate washing area motor Pump I/P.

BILL OF MATERIAL / QUANTITIES - ELECTRICAL WORK - POONAMALLEE- CHENNAI							Project:	Electrical works	
DATE: 13.03.2026							Client :	YUSEN LOGISTICS (INDIA) PRIVATE LIMITED	
							Quote No:	QUOTE/25-26/1324	
S.No.	Description	Unit	Qty	Materials		Labour		Total	Remarks
				Rate	Total	Rate	Total		
7	Medium Voltage Panel							123,100	
	Floor / wall mounted Power Distribution Panel suitable for 415V, 3-phase, 4-wire, 50Hz AC supply,IP42 (minimum) Protection. Powder coated 1.6 mm thick CRCA sheet for doors & covers. Incomer- 250 A MCCB, 4 Pole, 36kA. Busbar- suitable for 250A Continuous duty. Out going - 63A 4 pole 10 kA MCB - 12 nos.Suitable for aluminium/copper cable termination. Digital multifunction meter & LED indication lamps for R-Y-B phase healthy Control MCB – 6A SP	Set	1	119,600	119,600	3,500	3,500	123,100	Main Power Distribution Panel
8	MV Armour cables - Make : Polycab / RR							251,250	
	3.5 Core x 70 sq.mm with END Terminations -Aluminum Cables	RMT	50	597	29,850	519	25,950	55,800	From Building panel to Power distrbtion Panel & DG
	4 core 16 sqmm AL. Cable with END Terminations- Aluminum Cables	RMT	150	222	33,300	369	55,350	88,650	All PDB I/p
	3C x 6 sqmm Cu. Cable with END Terminations - Copper cables	RMT	150	474	71,100	238	35,700	106,800	Cold Room
9	Raceways /Aluminum channels /Conduiting							208,000	
	150 mm x 50mm perforated Type	RMT	300	355	106,500	181	54,300	160,800	
	50 mm x 50mm perforated Type	RMT	50	218	10,900	106	5,300	16,200	
	25mm dia. PVC conduit	RMT	300	33	9,900	29	8,700	18,600	
	32mm dia. PVC Cassing Patty	RMT	100	59	5,900	44	4,400	10,300	
	25mm dia. PVC Cassing Patty	RMT	25	46	1,150	38	950	2,100	
10	Power Receptacles : Make: Anchor Roma / GM							114,358	
	1 No. 6A Independent Switched socket outlet	Nos	30	450	13,500	350	10,500	24,000	
	2 Nos 5Amps Intel multi pin socket outlets controlled by 1 Nos. 16A SP switch.	Nos	30	780	23,400	500	15,000	38,400	Work station Power Points
	3 Nos 5Amps Intel multi pin socket outlets controlled by 1 Nos. 16A SP switch.	Nos	15	910	13,650	500	7,500	21,150	Work station Power Points
	1No. 6/16A multi pin Independent Switched socket outlet	Set	10	650	6,500	300	3,000	9,500	For AC & Pedastal fan
	32A, 3Ph. 5pin industrial socket outlet controlled by a 32/40A TP MCB, inclusive of factory made metal box,etc., complete.	Set	1	6,183	6,183	900	900	7,083	For cleaning machine
	Supply and fixing of 63A FP MCB, inclusive of factory made out door / in door metal box,etc., complete.	Set	5	2,295	11,475	550	2,750	14,225	UPS I/P & O/P 4 nos + crate washing area power point 1 nos
11	Miscellaneous							57,500	
	Structural Steel Supports for lights, Panel caging etc.	Kg	250	125	31,250	65	16,250	47,500	Panel room Cage etc
	Transportation Charge for all above materials	No	1	10,000	10,000	-	-	10,000	
12	Grand Total							1,315,058	

Note:

- 1 GST Extra 18%
- 2 Any BOQ deviation the cost will be extra at actual.
- 3 Payment terms 50% Advance 50% After completion of the project.
- 4 Materials once sold will not be taken back or exchanged